

Recommended Practices for Installation of Underground Liquid Storage Systems



FOREWORD

These *Recommended Practices for Installation of Underground Liquid Storage Systems* have been prepared as an industry service by PEI. This recommended practice is truly an industry document, as PEI members, environmental regulators, oil company engineers, oil marketing trade associations, etc., have had an opportunity to review and comment on the previous publication under the same name. The text represents the consensus views of the PEI Tank Installation Committee, comprised of the following members:

Blake Bammer, Chairman

JF Petroleum Group
Morrisville, North Carolinaa

Carl E. Bayliss, II

B C & C LLC
Winchester, Virginia

Chris Collura

Guardian Fueling Technologies
Jacksonville, Florida

Ryan Haerer

U.S. Environmental Protection Agency
Washington, DC

Gina M. Jaimes

JF Petroleum Group
Fate, Texas

Randy D. Martin

PA Dept. of Environmental Protection
Harrisburg, Pennsylvania

Michael Mizicko

Western Pump Inc.
San Diego, California

David J. Piercy

JD2 Environmental Inc.
West Chester, Pennsylvania

Jimmy Spiros

Neumayer Equipment Co.
Saint Louis, Missouri

Bret Swan

Minnesota Petroleum Service Inc.
Minneapolis, Minnesota

This document supersedes and replaces the previous recommended practice entitled, *Recommended Practices for Installation of Underground Liquid Storage Systems*, PEI/RP100-2020.

All questions and other communications relating to this document should be sent only to PEI Headquarters, addressed to the attention of the PEI Tank Installation Committee.

PEI

P.O. Box 2380
Tulsa, OK 74101-2380
(918) 494-9696
info@pei.org
www.pei.org
© 2022 PEI

CONTENTS

Foreword	iii
----------------	-----

SECTIONS

	Page
1. Introduction	
1.1 Background	1
1.2 Purpose	1
1.3 Scope	1
1.4 Sources	1
1.5 Use of Other PEI Recommended Practices	1
1.6 Importance of Competent Installers	1
1.7 Written Plans	2
1.8 Unexpected Conditions	2
1.9 Corrosion Concerns	2
1.10 Regulations	2
2. Materials Handling.....	3
2.1 Care in Handling Tanks	3
2.2 Unloading, Lifting and Lowering	3
2.3 Tank Storage	3
2.4 Piping and Equipment Storage.....	3
3. Preinstallation Inspection and Tank Testing	4
3.1 Preinstallation Inspection	4
3.2 Preinstallation Tank Testing	4
3.3 Preinstallation Testing of Double-Walled Tanks	5
3.4 Preinstallation Testing of Compartmented Tanks	6
3.5 Alternative Interstice Tests	6
3.6 Double-Walled Tank With Liquid-Filled Interstice	6
3.7 Double-Walled Tank With Vacuum on Interstice.....	6
4. Earthwork	7
4.1 Earthwork	7
4.2 Excavation Location.....	8
4.3 Excavation Depth, Bedding and Backfill.....	8
4.4 Cover in Areas Subject to Traffic.....	8
4.5 Cover in Areas Not Subject to Traffic	9
4.6 Maximum Burial Depths	9
4.7 Handling of Excavated Materials	9
4.8 Work Area Safety	9
4.9 Used Tank Excavation	9
5. Backfilling	10
5.1 General	10
5.2 Ballasting	10
5.3 Water Management	10
5.4 Backfill Material for Steel, Composite (Fiberglass-Clad Steel) and Jacketed Tanks	10
5.5 Backfill Placement for Steel, Composite and Jacketed Tanks	11
5.6 Backfill Material for Fiberglass Tanks	11



5.7	Backfill Placement for Fiberglass Tanks.....	12
5.8	Compaction	12
5.9	Measuring Tank Deflection	12
5.10	Filter Fabric	12
5.11	Supporting Equipment During Construction	12
6.	Anchoring.....	13
6.1	General	13
6.2	Excavating Requirements.....	13
6.3	Wet-Hole Conditions.....	13
6.4	Anchorage Types	13
6.5	Straps	14
6.6	Electrical Isolation.....	15
6.7	Attachment Methods	15
7.	Spill Containment and Overfill Prevention	16
7.1	Purpose	16
7.2	Spill Containment.....	16
7.3	Overfill Prevention.....	16
7.3.1	Alarms	16
7.3.2	Flow Shutoff Devices.....	17
7.4	Overfill Device Installation.....	17
7.5	Remote Fills	17
8.	Secondary Containment	18
8.1	Purpose	18
8.2	Double-Walled Spill Buckets	18
8.3	Double-Walled Tanks	18
8.4	Double-Walled Piping	18
8.5	Containment Sumps	18
8.5.1	Tank-Top Sumps	19
8.5.2	Dispenser Sumps	19
8.5.3	Transition Sumps	19
8.5.4	Containment Sump Testing	19
8.6	Safety Considerations.....	20
9.	Leak Detection	21
9.1	Purpose	21
9.2	Double-Walled Tank Leak Detection.....	21
9.2.1	Interstitial Monitoring of Steel and Composite Tanks.....	21
9.2.1.1	Manual Interstitial Monitoring of Steel and Composite Tanks.....	21
9.2.1.2	Electronic Interstitial Monitoring of Steel and Composite Tanks	21
9.2.2	Interstitial Monitoring of Fiberglass Tanks.....	21
9.2.2.1	Manual Interstitial Monitoring of Fiberglass Tanks.....	21
9.2.2.2	Electronic Interstitial Monitoring of Fiberglass Tanks	21
9.3	Double-Walled Piping Leak Detection	22
9.3.1	Secondary Containment Monitoring	22
9.3.1.1	Manual Secondary Containment Monitoring	22
9.3.1.2	Electronic Secondary Containment Monitoring	22
9.3.2	Interstitial Monitoring	23
9.3.2.1	Manual Interstitial Monitoring	23
9.3.2.2	Electronic Interstitial Monitoring	23
9.3.3	Automatic Line Leak Detectors	23
9.3.4	Satellite Dispenser Piping	23
9.3.5	Under-Pump Check Valve.....	23

10. Piping and Fittings.....	25
10.1 General Requirements for Product Piping	25
10.2 Piping Materials	25
10.3 Piping Practices	25
10.4 Piping Layout and Trenches.....	25
10.5 Piping Backfill and Compaction	26
10.6 Flexible Connectors.....	26
10.7 Threaded Joints	26
10.8 Metallic Piping	27
10.9 Fiberglass Piping	27
10.10 Flexible Piping	28
10.11 Containment Sumps	28
10.12 Vent Piping	28
10.13 Fill Piping	28
10.14 Submersible Pump.....	29
10.15 Suction Stub	29
10.16 Emergency Shutoff Valves	29
10.17 Manifolded Tanks and Siphon Piping.....	30
10.18 Vapor Recovery Piping	30
10.19 Water Gauging Port.....	30
11. Testing Piping.....	31
11.1 Testing of Product Piping.....	31
11.1.1 Initial Test for Single-Walled Piping	31
11.1.2 Initial Test for Coaxial Piping	31
11.1.3 Monitoring During Construction	31
11.1.4 Post-Construction Testing	31
11.2 Testing Secondary Containment Piping	31
11.2.1 Initial Test for Secondary Piping	31
11.2.2 Monitoring During Construction	31
11.2.3 Final Integrity Test for Secondary Piping	32
12. Cathodic Protection Systems	33
12.1 General Requirements	33
12.2 Applicability	33
12.3 Factory-Installed Systems for Tanks	33
12.4 Dielectric Coatings	33
12.5 Electrical Isolation.....	33
12.6 Galvanic Anodes for Piping	34
12.7 Impressed-Current Systems.....	34
12.8 Test Stations	34
12.9 Wiring and Electrical Connections	35
12.10 Piping	35
12.11 Protecting Piping	35
12.12 Field-Applied Coating	36
12.13 Other Components.....	36
12.14 Inspection and Testing	36
13. Electrical Installation	37
13.1 Importance of Electrical Work	37
13.2 General Requirements	37
13.3 Leak Detection and Cathodic Protection Systems	37

14. Testing	38
14.1 System Tests	38
14.2 Cathodic Protection Systems.....	39
14.3 Test Results	39
14.4 Other Testing	39
15. Documentation and Training.....	40
15.1 ‘As-Built’ Drawings	40
15.2 Component Documentation.....	40
15.3 Installation Checklists	40
15.4 Scheduled Inspections and Maintenance	40
15.5 Training	40
Appendix A: Floatout and Anchorage Calculations	41
A.1 Purpose	41
A.2 Weight of Materials	41
A.3 Reflected-Tank Area.....	41
A.4 Tank Displacement.....	41
A.5 Reinforced Concrete Pad at Finished Grade	41
A.6 Depth of Burial to Top of Tank	41
A.7 Volume and Weight of Overburden.....	41
A.8 Adequacy of Restraining Forces	42
A.9 Calculation of Safety Factor	42
A.10 Effect of Adding 1 Foot to Burial Depth	43
A.11 Applicability	43
Appendix B: Background: Cathodic Protection	44
B.1 Galvanic Corrosion	44
B.2 Stray-Current Corrosion	44
B.3 Rate of Corrosion	44
B.4 Coatings.....	44
B.5 Cathodic Protection	44
B.6 Impressed-Current Systems.....	44
B.7 Galvanic Anodes	45
B.8 Anode Backfill Material.....	45
B.9 Magnesium Anode Selection.....	45
B.10 Calculation of Anode Life.....	45
B.11 Number of Feet of Well-Coated Steel Pipe Protected With One Galvanic Anode.....	46
B.12 Adjusting Factors for Anodes Installed in Parallel	46
Appendix C: Publication Reference	47