

Recommended Practices for the Closure of Underground Storage Tank and Shop-Fabricated Aboveground Storage Tank Systems



CONTENTS

Foreword iii

SECTIONS

	Page
1. Introduction	1
1.1 Origin	1
1.2 Background.....	1
1.3 Purpose.....	1
1.4 Scope.....	1
1.5 Sources.....	1
1.6 Use of Other PEI Recommended Practices.....	2
1.7 Regulations and Codes.....	2
1.8 Importance of Competent Technicians.....	2
1.9 Training.....	2
1.10 Notifications/Permits.....	2
2. Safety	3
2.1 General.....	3
2.2 Safety and Health Program.....	3
2.3 Safety Plan.....	3
2.4 Lifting Equipment.....	3
2.5 Rigging.....	3
2.6 Fall Protection.....	3
2.7 Electrical Hazards.....	3
2.8 Fire and Explosion Hazards.....	3
2.8.1 Static Electricity.....	4
2.9 Testing for Flammable Vapors.....	4
2.10 People Hazards/Public.....	4
2.11 Work Area Protection.....	4
2.12 Vehicle Hazards.....	5
2.13 Test Equipment.....	5
2.14 Confined Space Entry.....	5
2.15 Spill Response.....	5
2.16 Excavation Safety.....	5
2.17 Excavation Cave-Ins.....	5
2.18 Additional Excavation Hazards.....	6
2.19 Climate/Weather.....	6
2.20 Personal Protective Equipment (PPE).....	6
2.21 Protective Equipment Types.....	6
3. Vacuum Equipment (Trucks and Self-Contained Vacuum Equipment)	7
3.1 General.....	7
4. Underground Storage Tanks	8
4.1 Closure Methods.....	8
4.1.1 Temporary Closure.....	8
4.1.2 Permanent Closure.....	8
4.2 Temporary Closure.....	8
4.2.1 Notification.....	8
4.2.2 Tasks.....	8

4.3	Pre-Closure Evaluation.....	8
4.4	Permanent Closure in Place	9
4.4.1	Notification	9
4.5	Permanent Closure by Removal	9
4.5.1	Notifications	9
4.5.2	Pre-Closure Evaluation.....	9
4.5.3	Product Removal From Piping and Tank	9
4.5.3.1	Product Removal From Piping.....	10
4.5.3.2	Product Removal From Tank	10
4.5.4	Ancillary Equipment Removal	10
4.5.5	Spill Response	10
4.5.6	Water Removal	10
4.5.7	Excavation to Tank Top.....	11
4.5.8	Leaving Tank in Excavation	11
4.5.9	Cleaning Inside Tank	11
4.5.10	Vapor-Freeing Tank	11
4.5.10.1	Purging	11
4.5.10.2	Inerting	12
4.5.10.2.1	Inerting With Nitrogen.....	12
4.5.10.2.2	Inerting With CO ₂	12
4.5.10.3	Encapsulation	13
4.5.10.4	Vapor-Freeing Tank With Water	13
4.5.10.5	Tank Monitoring.....	13
4.5.10.6	Interstitial Monitoring	13
4.5.11	Accessing Tank Interior.....	13
4.5.12	Tank Removal From Excavation	14
4.5.13	Piping Removal	14
4.5.14	Water Removal	14
4.5.15	Excavation Backfilling	14
4.5.16	Removed Tank Management	14
4.5.16.1	Tank Removal From the Site	14
4.5.16.2	Tank Destruction On-Site.....	15
4.6	Permanent Closure In Place	15
5.	Aboveground Storage Tanks.....	16
5.1	General	16
5.2	Removal From Service	16
5.2.1	Tasks.....	16
5.2.2	Cleaning Inside Tank	16
5.2.3	Vapor-Freeing Tank.....	16
5.2.3.1	Purging	16
5.2.3.2	Inerting	17
5.2.4	Encapsulation	18
5.2.5	Vapor-Freeing Tank With Water	18
5.2.6	Tank Monitoring	18
5.2.7	Interstitial Monitoring	18
5.2.8	Accessing Tank Interior (Optional)	19
5.2.9	Transporting Tank	19
5.2.10	Returning Temporary Out of Service ASTs to Operation.....	19
5.2.11	ASTs that are not Suitable to be Returned to Service	19
5.3	UL 2085 Aboveground Storage Tank	19
6.	Disposal.....	21
6.1	Disposal Requirements	21
6.2	Recycling Scrap Metal	21
6.3	Landfill and Other Disposal Sites	21

7. Documentation and Recordkeeping..... 22

- 7.1 General22
- 7.2 Tank Closure Report22
- 7.3 Record Retention22

Appendix A: Electrical Disconnection Procedures 23

- A.1 Electrical disconnection for temporary closure23
- A.2 Electrical disconnection for permanent closure23

Appendix B: Publication Reference 24